Slabbed tunnel of 5 vents of 5' x 5' of Bangalore-Bellary Road.

Sl. No.	Items of work	Per	Quantity	Rate
				Rs. a. p.
1	Earthwork cutting top earth using old materials and gravel to deviation road and consolidating.	C.yds.	97	
2	Dismantling old masonry and carting debris ...	C.ft.	6,238	
3	Removing old apron and rebuilding in places required	C.yds.	57	
4	Earthwork excavation foundation and forming banks	"	64	
5	Stone jelly concrete in surki mortar foundation ...	C.ft.	1,732	
6	Burnt stone in surki mortar foundation Depth 7' ...	"	2,955	
7	Burnt stone superstructure with lift of 6' ...	"	3,201	
8	Burnt stone slabs 8" to 9" for covering roughly dressed with close joints with lift and lead of 6 miles	S.ft.	770	
9	Burnt stone slabs 6" thick dressed and fixed and lead of 6 miles.	"	939	
10	Burnt stone in surki mortar Δ cut water to piers and lead of 6 miles.	C.ft.	44	
11	Two line dressing to coping slab fixed with mortar.	S.ft.	360	
12	Guard stones top rounded and dressed with fixing...	Each	8	
13	Cement pointing exposed portion	Sqr.	31·02	
14	Forming road-way with gravel carted	C.yds.	65	
15	Metalling the roadway with burnt metal and consolidation.	"	38	
16	Sundry works such as baling water during execution	Lump	sum	
17	Size stone revetment new with jelly backing ...	C.yds.	52	
18	Clearing draft channel	Lump	sum	
19	Stone cap over cut water and piers	Each	8	

H. R. VENKATASUBBA RAO,
Executive Engineer.

KOLAR DIVISION.

Dated 24th January 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 17th February 1930, for restoring Nandamballi Tamatanakunte, R. No. 118—870 of Kolar Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate, and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below showing the rates, at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and seventy-five in cash or Government Promissory Notes as earnest money and be superscribed "Tender for restoring Nandamballi Tamatanakunte R. No. 118—870 of Kolar Taluk" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection or any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. The tenderer must quote specific rates for each item of work both in words and in figures.

10. The tenderer stating that the work would be executed at a certain percentage in excess of or lower than the estimate will not be accepted.

Abstract estimate for restoring Nandamba'h Tamatankunte Reg. No. 118—870 of dar Taluk.

Serial No.	Items of work	Per	Rate	Quantity
			Rs. a. p	
	Bund.			
1	Earthwork with watering and tamping, etc., for consolidation with lead and lift complete.	C.ft.	...	4,568
2	Turfing	S.yds.	..	3,461
3	Removing and resetting old stone work ..	,,	..	635
4	New stone work	,,	...	518
5	Grade stones including painting, figuring, etc., complete.	No.	...	15
5	Index stones do	,,	...	15
7	Gauge stones do	,,	..	1
8	Bench mark stones do	,,	...	...
9	Cutting trenches and removing prickly pears jungle with roots anthills, etc.	Grade	..	8
10	Examining and closing leaks in lead... ...	Lump	sum	...
	Total ...	...	...	...
	Sluice.			
1	Examining and repairing by providing new plug with rod with locking arrangements.	Lump	sum	...
	Total ...	...	...	...
	Constructing a masonry weir to a length of 71 feet at 51·50.			
1	Earthwork excavation	C.yds.	...	378
2	Filling the scour with excavation earth as above ...	...	...	378
3	Concrete in surki mortar	C.ft.	...	180
4	Burnt brick in surki mortar	,,	..	265
5	Burnt stone slabs 6" thick...	S.ft.	...	315
6	Plastering with surki mortar	Sqr.	..	4·50
7	New stone work	C.yds.	..	75
	Total ...	...	..	...
	Total of bund sluice and weir ...	...	...	...
	Grand total ...	..	...	...
	Contingency at 5 per cent ...	...	...	...
	Grand total ..	..	..	...

Abstract Notification dated 9th January 1930.

The attention of the public is invited to the notification, published in the *Mysore Gazette*, Part VI, pages 61 and 62, dated 16th January 1930, calling for tenders for constructing a Mahadwaram to Sri Venkataramanaswamy Temple at Guttahalli, Bowringpet Taluk.

The last date for tender is 1st February 1930.

Abstract Notification dated 9th January 1930.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, pages 60 and 61, dated 16th January 1930, calling for tenders for restoring Chakarasan (Main Gonikere Regd. No. 93/643 of Malur Taluk.

The last date for tender is 2 P.M. of 1st February 1930.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.